

3 022678

15-207-19464-00-00

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040041
SE,NW,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.
1446 feet from south section line
4356 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# APT NO. CT-A
County WOODSON
Well Total Depth 1000' feet

Name & FEE FUND PLUGGING
Address _____

Production Pipe: 2" Size Feet 1000'
Surface Casing: 10" Size Feet 20'

AB oil well X Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE Lic. # 6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00A.M. Day: 21 Month: 1 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HAD
BEEN CEMENTED IN AT T.D. ONLY. A STRING OF 1" ON A PACKER WAS IN 2" CASING.
THE PLUGGING PROPOSAL WAS TO REMOVE THE PACKER AND 1" AND TO CIRCULATE
AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All X Part _____ TECHNICIAN
None _____

Operations Completed: Hour: 12:00P.M. Day: 21 Month: 1 2005

Actual Plugging Report: THE PACKER AND 1" TUBING WERE REMOVED FROM THE
WELL. THE 2" CASING THEN COLLAPSED DOWN THE WELL BORE. A 7" SWEDGE WAS
RAN INTO THE 10" SURFACE CASING TO 400' WITHOUT ENCOUNTERING AN OBSTRUCTION.
THE SWEDGE WAS REMOVED. 1" PIPE WAS RAN INTO THE WELL TO 525'. A SOLID
OBSTRUCTION WAS ENCOUNTERED AT THAT DEPTH. CEMENT WAS PUMPED INTO THE
1" PIPE UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE. THE 1" WAS REMOVED.
264 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO. 48) (THIS WELL WAS NO. CT-A ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

FEB 02 2005

KCC WICHITA

bn