

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-00440-00-01  
Spot: NENE Sec/Twnshp/Rge: 27-16S-25W  
4592 feet from S Section Line, 569 feet from E Section Line  
Lease Name: FREVELE B OWWO Well #: 1  
County: NESS Total Vertical Depth: 4532 feet

Operator License No.: 5088  
Op Name: DARRAH, JOHN JAY, JR.  
Address: 225 NORTH MARKET, STE 300  
WICHITA, KS 67202

L1 Size: 4.5 feet: 4526 WITH 50 SX CMT  
PROD Size: 7 feet: 4510 1193' PULLED 9/1/72  
SURF Size: 10.75 feet: 297

29  
\$ 147

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2005 9:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4460' & 4 SX CMT. PLUG AT 1200' WITH 20 SX GEL & 100 SX CMT. PLUG AT 600' WITH 75 SX CMT. PLUG AT 330' WITH 75 SX CMT. PLUG AT 40' WITH 20 SX CMT

Plugging Proposal Received By: RICHARD LACEY  
Date/Time Plugging Completed: 01/25/2005 1:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SAND TO 4460' WITH 4 SX CMT. 1ST PLUG RIPPED CASING AT 1200' & PUMPED 20 SX GEL & 100 SX CMT. WAIT 45 MINUTES. 2ND PLUG AT 600' WITH 75 SX CMT. 3RD PLUG AT 330' WITH 75 SX CMT. 4TH PLUG TOP OFF WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4512	4516		

RECEIVED  
FEB 04 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 604' OF 4 1/2" CASING

Plugged through: CSG

District: 01



Signed Michael J Maier  
(TECHNICIAN)

INVOICED  
DATE 2.4.05  
INV. NO. 2005061149