

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-26653-00-00
Spot: E2E2W2NE Sec/Twnshp/Rge: 36-33S-10E
1320 feet from N Section Line, 1490 feet from E Section Line
Lease Name: MCCANN Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 814 feet

Operator License No.: 33472
Op Name: 3-D OIL COMPANY
Address: 215 E. MAIN ST.
SEDAN, KS 67361

SURF Size: 8.625 feet: 80

\$ 35⁰⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/26/2005 12:00 PM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S INC. Phone: (620) 249-2519

Proposed Plugging Method: TO PUMP CEMENT & GEL FOR BOTTOM & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: NONE
Date/Time Plugging Completed: 01/26/2005 3:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

WASHED 1" HYDRIL TUBING DOWN 6.8750" OPEN HOLE TO 750' & HIT HARD WELL CUTTINGS (PBTD). PUMPED THRU 1" & GELLED HOLE, THEN PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" UP TO 500' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" OUT (1" HYDRIL HUNG-UP - PARTED/PULLED APART IN CEMENT & LOST 12 JOINTS 1" IN HOLE) & TOPPED-OFF WELL. USED TOTAL OF 141 SACKS CEMENT & 2 SACKS GEL.

Perfs:

RECEIVED
KCC DISTRICT #3

JAN 31 2005

CHANUTE, KS

RR


INVOICED
DATE 2.7.05
2005061154

Remarks: THIS WAS SUPPOSED TO BE AN 1800' OIL WELL, BUT HOLE WAS DRILLED WITH AN "AIR" DRILLING RIG & "WATERED-OUT" @ 814'. OPERATOR DECIDED TO PLUG HOLE.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED
FEB 07 2005
KCC WICHITA