

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24805-00-00
Spot: NESENW Sec/Twnshp/Rge: 13-20S-11W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BARBER Well #: 1
County: BARTON Total Vertical Depth: 3312 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3300 150 SX CMT
SURF Size: 8.625 feet: 326 225 SX CMT

#10764

Well Type: ~~OH~~ DH ^{Per ACD-1} 2-7-05 UIC Docket No: _____ Date/Time to Plug: 01/31/2005 1:00 PM
Plug Co. License No.: 31529 ^{Kee} 136m Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 793-3051

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 400# hulls.
Dakota 0' - 320'. Anhy. 451' - 465'. Salt 951' - 1241'.
Tested and non-commercial.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2005 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Kelso sanded off bottom to 3250' and topped with 5 sxs cement using a dump bailer.
Ran in hole and cut casing at 2560'. Pulled to 1275'.
Allied rigged onto casing and pumped 90 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled casing to 500' - pumped 40 sxs 60/40 pozmix with 100# hulls mixed in.
Pulled casing to 150' - pumped 40 sxs to circulate cement to surface.
POOH. Pulled rest of casing. Hole standing full.
Used 170 sxs cement and 400# hulls.

Perfs:

Top	Bot	Thru	Comments
3301	3309		

RECEIVED
FEB 07 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

ND

Signed *Patrick Ford*
(TECHNICIAN)

INVOICED

DATE 2.7.05

INV. NO. 2005061156

FEB 01 2005