

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21518-00-00
Spot: SWNESWSW Sec/Twnshp/Rge: 4-29S-15W
680 feet from S Section Line, 4320 feet from E Section Line
Lease Name: BOLSER RG Well #: 7
County: PRATT Total Vertical Depth: 4902 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S. MAIN, STE 420
WICHITA, KS 67202

PROD Size: 5.5 feet: 4899 WITH 350 SX CMT
SURF Size: 8.625 feet: 402 WITH 300 SX CMT

32
\$159

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2005 4:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4650' & 5 SX CMT. PLUG AT 1200' WITH 15 SX GEL - 50 SX CMT - 100# HULLS. PLUG AT 430' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2005 6:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4650' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 930' WITH 10 SX GEL - 50 SX CMT W/100# HULLS. 2ND PLUG AT 430' WITH 50 SX CMT W/100# HULLS. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4700	4714		

RECEIVED
FEB 07 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2628' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Pfeifer
(TECHNICIAN)

INVOICED
DATE 2-7-05
INV. NO. 2005061157

Form 0125