

3 022682

15-207.19467.00.00

To:  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040041  
SW,NE,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.  
1900 feet from south section line  
3812 feet from east section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: STATE OF KANSAS Fee Fund

Lease/Well# APT 33  
County WOODSON

Name & FEE FUND PLUGGINGWell Total Depth 1000' feet

Address \_\_\_\_\_

Production Pipe: 2" Size Feet 1000'Surface Casing: 8" Size Feet 20'AB oil well X Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_

D &amp; A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE Lic. # 6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 10:00A.M. Day: \_\_\_\_\_ 18 Month: \_\_\_\_\_ 1 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HAD  
BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS  
MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All X Part \_\_\_\_\_TECHNICIAN  
None \_\_\_\_\_Operations Completed: Hour: 12:00P.M. Day: \_\_\_\_\_ 18 Month: \_\_\_\_\_ 1 2005Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING ATSURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUSTO 575'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THESURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WASFILLED FROM SURFACE. 265 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

FEB 02 2005

Remarks: (GPS SESSION PT. NO. 78 ) ( THIS WELL WAS NO.33 ON THE LEASE MAP. )

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I DID observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN