

10-5

To: **6 041232**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-20,326 20-01

NW NE SE, SEC. 4, T. 6 S, R. 20 W/E<sub>x</sub>

2310 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

5015

Operator License # \_\_\_\_\_

Lease Name Witt Well # 1

Operator: Hellar Drilling Co. Inc.

County \_\_\_\_\_ Rooks 117.32

Name & Address: 125 N. Market

Well Total Depth 3610 feet

S. 1422

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita, Ks. 67202

Surface Casing: Size 8 5/8 feet 207 w/150 sk

Abandoned Oil Well xx Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: 10:00 AM Day: 5 Month: Oct. Year: 19 90

Plugging proposal received from Carl Gilpin

(company name) Hellar Drilling (phone) \_\_\_\_\_

were: 4 1/2 casing set at 3579 w/125 sks cement: perfs at 3452 to 3505;

Perf anhy at 1710; perf base dakota at 850. Ordered 350 sks 65/35 poz 10% gel w/ 1/4 lb f.c.

plus 500 lbs. hulls.

Plugging Proposal Received by Dennis Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30PM Day: 5 Month: October Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 4 1/2 casing w/25 sks cement w/ 1/4 lb f.c. plus

pumped in add 275 sks cement w/ 1/4 lb f.c. and 4 sks hulls mixed in cement.

Max 500 lbs. S.I. 1 300 lbs. Pumped in 8 5/8 casing w/50 sks cement w/ 1/4 lb f.c. and

1 sk hulls mixed in cement. Max 400 lbs. S.I. 300 lbs.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE OCT 23 1990

INV. NO. 29694

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 17 1990  
Dennis L. Hamel  
(TECHNICIAN)  
Dennis L. Hamel  
CONSERVATION DIVISION  
Wichita, Kansas