

3 022680

15-207.19469-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040041

SW,NE,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

1675 feet from south section line

3777 feet from east section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS Fee Fund

Name &amp; FEE FUND PLUGGING

Address

AB oil well X Gas Well SWD Well/ Input Well

Lease/Well# APT NO. 51

County WOODSON

Well Total Depth 1000' feet

Production Pipe: 2" Size Feet 1000'

Surface Casing: 6" Size Feet 20'

D &amp; A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE Lic. # 6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00A.M. Day: 19 Month: 1 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HAD

BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO

CIRCULATE THE CASING FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part Technician None X

Operations Completed: Hour: 11:00A.M. Day: 19 Month: 1 2005

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 3/4" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

40 SACKS OF CEMENT WERER PUMPED INTO THIS WELL.

RECEIVED

FEB 02 2005

KCC WICHITA

Remarks: (GPS SESSION PT. NO. 51) ( THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP. )

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN

B