

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23369-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 6-6S-20W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: MORRIS TRUST Well Number: 1  
County: ROOKS Total Vertical Depth: 3509 feet

Operator License No.: 31514  
Op Name: THOROUGHbred ASSOCIATES L.L.C.  
Address: 8100 E. 22ND ST. - BUILDING 600  
WICHITA, KS 67226

Surface Casing Size: 8.625 feet: 355 **\$ 114.04**

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/26/2003 8:30 AM  
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.  
Proposal Rcvd. from: DURAN MARKHEIM Company: L.D. DRILLING, INC. Phone: (620) 793-4064

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.  
No arbuckle.

Plugging Proposal Received By: PAT STAAB Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 02/26/2003 9:30 AM KCC Agent: PAT STAAB

**Actual Plugging Report:**

1st. Plug at 1600' w/25 sxs cement.  
2nd. Plug at 1005' w/100 sxs cement.  
3rd. Plug at 405' w/40 sxs cement.  
4th. Plug at 40' w/10 sxs cement. 8 5/8" wiper plug.  
Rathole with 15 sxs.  
No Mousehole.

RECEIVED  
MAR 06 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed  (TECHNICIAN)



**INVOICED**

Form CP-2/3

DATE 3-6-03

INV. NO. 200 306 1276

**MAR 04 2003**