

4-041647

11-17

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,311-00-00

SW SW NE /4 SEC. 06, 06 S, 20 W
2970 feet from S section line
2970 feet from W section line

Operator license# 5242 Lease McClurg well # 3

Operator: Petroleum Management, Inc. County Rooks

Address: 14201 East Central Well total depth 3487 feet
Wichita, Kansas 67230 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 238 feet
w/200 sxs.

113.33

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing Co., Inc. License#

Address: P.O. Box 31 - Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 17 Month: November Year: 94

Plugging proposal received from: Don Keener

Company: Petroleum Management, Inc. Phone: 316-733-5600

Were: 4 1/2" casing set @ 3486' w/300 sxs. cmt. Perf. @ 3207' - 3315'.
Anhy. at 1620' - Dakota at 1000' - W.L.M. at 3210'.
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 17, Month: November, Year: 94

Actual plugging report: R.I.H. with tubing to 1750'. Spotted 100 sxs. cement w/100# hulls to circulate at surface. Pulled tubing and squeezed 4 1/2" casing w/100 sxs. cement w/200# hulls in cement. Max. P.S.I. 700#. S.I.P. 200#. 8 5/8" S.P. - squeezed w/50 sxs. cement and 100# hulls. Max. P.S.I. 800#. S.I.P. 300#.

STATE CORPORATION COMMISSION RECEIVED

JAN 13 1995

1-13-95

Remarks:
Condition of casing(in hole):GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did X did not observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE 1-18-95

INV. NO. 40370