

4-041646

11-17

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-21,184 -00-00

1650 SE NE SW /4 SEC. 06, 06 S, 20 W  
2970 4290 feet from S section line  
330 feet from E section line

Operator license# 5242 Lease Wallgren "A" well # 1

Operator: Petroleum Management, Inc. County Rooks

Address: 14201 East Central Well total depth 3485 feet <sup>113.26</sup>  
Wichita, Kansas 67230 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 223 feet  
w/100 sxs.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing Co., Inc. License# \_\_\_\_\_

Address: P.O. Box 31 - Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 17 Month: November Year: 94

Plugging proposal received from: Don Keener

Company: Petroleum Management, Inc. Phone: 316-733-5600

Were: 4 1/2" casing set @ 3484' w/160 sxs. cmt. Perf. @ 3226' - 3389'.  
Anhy. at 1620' - Dakota at 1000' - W.L.M. at 3157' - T.O.F. at 20'.  
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 11:00A.M., Day: 17, Month: November, Year: 94

Actual plugging report: Run tubing to 1800'. Spotted 100 sxs. cement  
with 100# to circulate cement at surface. Pulled tubing and squeezed  
4 1/2" casing w/100 sxs. cement w/200# hulls in cement. Max. P.S.I.  
500#. 8 5/8" S.P. - squeezed w/50 sxs. cement and 200# hulls.  
Max. P.S.I. 500#. S.I.P. 200#.

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
JAN 7 3 1995

1-13-95

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD  Anhy. plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC , NO \_\_\_\_\_ Dakota plug: YES  NO \_\_\_\_\_  
Plugged through TUBING , CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL \_\_\_\_\_

I did  / did not  observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE 1-18-95

INV. NO. 40269

#D