

Called 8/6/84 See toin message

6010092

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22355-00-00

SW, Sec. 4, T 6 S, R 20 W
330 feet from #1/S section line

2310 feet from W/S section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5752

Lease Name Steel Well # B-1

Operator: Name & Address
W. E. Carl
500 N. Water
Corpus Christa Texas
512-888-4171

County Rooks

Well Total Depth 3627 feet 117.88

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pioneer Drilg. Co. License Number 5665

Address Plainville Ks.

Company to plug at: Hour: 1 AM Day: 23 Month: 4 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO John Walker

(company name) Pioneer Drilg. Co. (phone) 913 434 4686

were: order 185 sx. cement. 50/50 pozmix 6% gel. 3% cc.

1 sx hulls 1-8 5/8 plug 1 sx. Flow Seal

Heavy mud between all plugs.
Pump cement down drill pipe

Elev. - 2157 Anhydrite 1751-79 Arbuckle No.

Dakota - 1400
757 = 1060
Signed Dale F. Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 8:30 AM Day: 23 Month: 4 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 1760 For 20 mi.

25 SX @ 1760

100 SX @ 1060 mixed with 1 sx. Flow Seal

40 SX @ 310

1 sx hulls pushed plug to 40'

10 SX @ 40

10 SX in Rat hole.
Remarks:

Cementing Co. Allied.

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1984
4-30-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated

and that I (did did not) observe this plugging.

Signed Dale F. Balthazor (TECHNICIAN)

INVOICED

DATE 4-30-84

INV. NO. 1285

4-23 MAY 09 1984 JUL 17 1984

FORM CP-2/3
Rev. 9-82