

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23088-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 10-21S-11W  
2491 feet from S Section Line, 927 feet from W Section Line  
Lease Name: SLEEPER Well #: 2-10  
County: STAFFORD Total Vertical Depth: 3450 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 9431 E CENTRAL, SUITE 100  
WICHITA, KS 67206

PROD Size: 4.5 feet: 3446 WITH 200 SX CMT  
SURF Size: 8.625 feet: 220

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/04/2004 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 2248' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/04/2004 10:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3383'. ANHYDRITE @ 492'. SANDED BOTTOM TO 2248' & 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 260' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3086	3096		

RECEIVED  
FEB 09 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1461' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Richard W. Lacey*

(TECHNICIAN)

INVOICED

DATE

8-10-04

WV. NO.

2005060338