

11-10

12  
R

4-031873

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-22,370-00-00

S2 NW SE SW /4 SEC. 08, 06 S, 20 W  
562 feet from S section line  
3535 feet from E section line

Operator license# - 101 Lease Brumbaugh well # 1

Operator: State of Kansas County Rooks

Address: 2301 E. 13th Street Well total depth 3850 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Fee Fund - Brumbaugh Project Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 10 Month: November Year: 93

Plugging proposal received from: Carl Goodrow - Dennis Hamel  
Herb Deines - Don Butcher

Company: State of Kansas - KCC Phone: 913-628-1200

Were: Order 225 sxs. 65/35 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 10:00A.M., Day: 10, Month: November, Year: 93

Actual plugging report: 8 5/8" set @ 250' cwc. 4 1/2" set @ 3580' with  
NA. D.V. @ 1700' cwc. to surface. Prod. PF. LKC. Squeezed 4 1/2" with  
225 sxs. cement blend with 500# hulls mixed in to Max. P.S.I. 1000#.  
Close in P.S.I. 700#. Tested 8 5/8" with 1/2 bbl. to 300#. Cement near  
surface. Plug complete.

RECEIVED  
STATE CORPORATION COMMISS

NOV 12 1993  
11-12-93

CONSERVATION DIVISION  
Wichita, Kansas

Remarks:  
Condition of casing(in hole): GOOD X BAD     Any plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

I did[ X ] / did not[     ] observe the plugging. Carl Goodrow

HO.

(agent)  
Form CP-2/3