

4-041947

1-5

API Number: 15-163-21212-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NE NE SW /4 SEC. 12, 06 S, 20 W  
2590 feet from S section line  
~~330~~ 2970 feet from E section line

Operator license# 41122

Lease: Hansen Trust Well # A-4

Operator: Doe's Well Service

County: Rooks 119.60

Address: P.O. Box 588  
Russell, Kansas 67665

Well total depth 3680 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 2940 Feet  
W/200 sxs cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Co Tools License# 41122

Address: P.O. Box 588 - Russell, Kansas 67665

Company to plug at: Hour: 12:00 P.M. Day: 5 Month: January Year 1998

Plugging proposal received from: Brian Reddig

Company: Doe's Well Service Phone: -

Were: 4 1/2" casing set at 3678' w/200 sxs cement. Perfs at 3620' - 3623'.  
Ordered 300 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.  
Anyh at 1750' - Dakota at 1075. Tubing fish at 2130'.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All  , Part [ ] , None [ ]

Completed: Hour: 4:00 P.M., Day: 5, Month: January, Year: 1998

Actual plugging report: R.I. H. with tubing to 1800'. Spotted 100 sxs cement with 450# hulls to circulate cement at surface. P.O.O.H. with tubing. Squeezed 65 sxs cement. Max. P.S.I. 400#. S.I.P. 200#. Squeezed 8 5/8" S.P. with 35 sxs cement with 50# hulls in cement. Max. P.S.I. 500#.

Remarks:

Condition of casing(in hole): GOOD - BAD   
Bottom plug(in place): YES  , CALC \_\_\_\_\_ , NO \_\_\_\_\_  
Plugged through TUBING  CASING \_\_\_\_\_

Anyh.plug: YES  NO \_\_\_\_\_  
Dakota plug: YES  , NO \_\_\_\_\_  
Elevation: \_\_\_\_\_ G.L.

I did  / did not [ ] observe the plugging.

*Dennis L. Hamel*  
STATE (agent)  
Form CP-2/3

INVOICED

DATE 1-12-98  
INV. NO. 49910  
1-5

JAN 9 1998  
1-9-98