

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-19147-00-00  
Spot: E2NENE Sec/Twnshp/Rge: 4-14S-15W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: DORTLAND C Well #: 0-53  
County: RUSSELL Total Vertical Depth: 3286 feet

Operator License No.: 31428  
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL  
Address: PO BOX 417  
VICTORIA, KS 67671

PROD Size: 5.5 feet: 3285  
SURF Size: 8.625 feet: 253

#106<sup>80</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/01/2005 9:00 AM

Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: JEFF CRAWFORD Company: LONESTAR OIL COMPANY Phone: (785) 735-2625

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Fluid level 200'. CIBP 3110'. Perfs 2730'.  
Squeezed 1982 - 1722' - 2080' w/300 sxs.  
Squeezed 1983 - 1700' w/200 sxs.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/01/2005 11:00 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 2000'.  
Allied pumped 160 sxs 60/40 pozmix - 10% gel with 600# hulls. Cement circulated.  
PTOH. Allied pumped 60 sxs cement.  
Max. P.S.I. 100#. S.I.P. 100#.  
Hooked up to backside and pumped 35 sxs cement with 100# hulls.  
Max. P.S.I. 500#. S.I.P. 500#.

RECEIVED  
FEB 07 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

2.7.05

INV. NO

2005061155

FEB 03 2005

HOME-STAKE PROD

PO-53 OORTLAND 'C'

4-14-15M  
E2 NE NE

Contr A L JACKSON

RUSSELL

County

E 1881 KBComm 9/20/63

Comp 1/9/64

TP OUYE (LANS 3119-27)

LOG Type	Depth	Datum
Anh Top	913	+968
Anh base	951	
LANS	3025	-1144
B KC	3272	-1391
GRAN W	3274	-1393
LTD	3286	-1405

Casing

8" 253:

5" 3285:

NO TESTS:

15/3119-27: A 1000: SWB 40 BPPM,  
31% OIL:

GORMAN

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHTA, KANSAS