

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21137-00-00
Spot: CS2SWNE Sec/Twnshp/Rge: 12-6S-20W
2970 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: GARTRELL A Well Number: 1
County: ROOKS Total Vertical Depth: 3593 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 5893 SADDLE CREEK TRAIL
PARKER, CO 80134

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 303 w/125 sxs cmt **\$116.77**
Production: Size 4.5 feet: 3590 w/150 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/01/2001 1:00 PM

Plug Co. License No.: 31725 Plug Co. Name: SHELBY RESOURCES LLC

Proposal Rcvd. from: CHRIS GOTTSCHALK Company: SHELBY RESOURCES LLC Phone: (303) 840-2183

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/01/2001 4:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1790'.
Allied pumped 50 sxs 60/40 pozmix - 10% gel, followed with 85 sxs 60/40 pozmix - 10% gel with 500# hulls.
Cement circulated. PTOH.
Allied pumped 35 sxs cement. Circulated out backside.
Shut in and squeezed 100 sxs.
Max. P.S.I. 150#. S.I.P. 100#.
Note: Emergency plug orders given with rig over the hole.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

RECEIVED

OCT 04 2001

KCC WICHITA

OCT 02 2001

INVOICED

DATE 10-4-01

INV. NO. 2002060728

GEODESSA-W E CARL-HAWN BROS- APC 12-6-20W
 #600 ONE MAIN PLACE #1 GARTRELL "A" C S/2 SW NE
 WICHITA, KS 67202
 CONTR PIONEER DRILLING CO CTY ROOKS

GEOL _____ FIELD EDGAR EAST EXT (1/8 E)

E 2125 KB CM 9/30/80 CARD ISSUED 10/29/81 IP P 42 BOPD & NW
 2120 GL 15-163-21,137 REAG SD OH 3590-3594

+	+
+	+
+	+

LOG	TOPS	DEPTH	DATUM
*ANH		1706	+ 419
*B ANH		1742	+ 383
HEEB		3305	-1180
LANS		3343	-1278
B KC		3540	-1475
GOR		3583	-1458
REAG		3587	-1462
REAG POR		3589	-1464
RTD		3593	-1468
LTD		3594	-1469

8-5/8" 303/125sx, 4 1/2" 3590/150sx
 DST (1) 3582-3593(GOR)/30-30-30-60,
 300' GIP, REC 150' O&GCM, SIP 1074-
 1061#, FP 0/75-86#, HP 1886-1876#,
 BHT 1110
 DST (2) 3582-3593(REAG)/MISRUN
 DST (3) 3579-3583(REAG)/MISRUN
 MICT - CO, (REAG OH) 3590-94, SWB
 DWN, SWB 3/HR @ 1.75 BOPH, ONFU
 2590', 1000' O, SWB DWN & REC 42 BO,
 NW, POP, P 40 BOPD, 1/21/81.

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS