


15-163-00904-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rooks County. Sec. 3 Twp. 6 Rge. 20W (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE NE SW  
Lease Owner C-G Drilling Co.  
Lease Name Witt Well No. 1  
Office Address 107 Rule Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 1 1959  
Application for plugging filed April 2 1959  
Application for plugging approved April 2 1959  
Plugging commenced April 2 1959  
Plugging completed April 2 1959  
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3645 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN  | PULLED OUT |
|-----------|---------|------|----|--------|---------|------------|
|           |         |      |    | 8-5/8" | 192.19' | none       |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 540'. Set plug. Put in 20 sacks cement. Filled to 185'. Set plug. Put in 1/2 sack hulls and 15 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sach hulls and 10 sacks cement.


RECEIVED  
STATE CORPORATION COMMISSION  
APR 7 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor C-G Drilling Co. 4-7-59  
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway  
107 Rule Building  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 1959



Vicky Jacobs  
Notary Public.

PLUGGING  
FILE SEC 3 T 6 R 20W  
BOOK PAGE 28 LINE 4

15-163-00904-00-00

WELL LOG

OPERATOR C-G Drilling Co. SEC. 3-6-20W  
 WELL NAME Witt #1 LOC. NE NE SW  
 TOTAL DEPTH 3645' COUNTY Rooks  
 COMM. March 23, 1959 COMP. April 2, 1959 STATE Kansas  
 RIG NO. 2 ELEVATION 2136' K.B.  
 CASING: Ran 192.19' (9 jts.) 8-5/8" OD Surface PRODUCTION: D & A  
 Casing.

All measurements taken from the top of rotary bushing.

| FROM | TO   | FORMATION   | DEVIATION FROM VERTICAL | REMARKS:       |
|------|------|-------------|-------------------------|----------------|
| 0    | 192  | Sand-Shale  |                         |                |
| 192  | 1505 | Shale-Sand  |                         |                |
| 1505 | 1915 | Red Bed     |                         |                |
| 1915 | 2260 | Shale-Shell | 0° - 2500               |                |
| 2260 | 3225 | Shale-Lime  | 0° - 2750               |                |
| 3225 | 3325 | Lime-Shale  | 0° - 3000               |                |
| 3325 | 3645 | Lime        | 0° - 3250               | DST 3608-3623' |

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 7 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 4-7-59

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 3rd day of April, 1959.

My commission expires: May 20, 1959

Wiley Jacobs  
Wiley Jacobs - Notary public

PLUGGING  
 FILE SEC 3 T 6 R 20W  
 BOOK PAGE 28 LINE 9