

15-163-02385-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 6 Twp. 6S Rge. (E) 20 (W)

Location as "NE/CNW/SE/SW" or footage from lines Approx. NW NE NW
Lease Owner Barnett Oil Company
Lease Name Vehige Well No. 1
Office Address 417 First Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 31, 1953
Application for plugging filed August 31, 1953
Application for plugging approved August 31, 1953
Plugging commenced August 31, 1953
Plugging completed August 31, 1953
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3542 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing				8 5/8"	155'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 3542 feet to 150 feet. Set wooden plug at 150 feet and filled surface casing with 1/2 sack of hulls and 15 sacks of cement to 103 feet. Filled surface casing with heavy mud from 103 feet to 40 feet. Set wooden plug at 40 feet and filled casing with 1/2 sack of hulls and 10 sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.
Address 623 First Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Hunter (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Hunter
417 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 19 53

My commission expires February 27, 1956.
Michael F. Willis Notary Public.

24-7368-5 3-53-20M

PLUGGING
FILE SEC 6 T 6 R 20W
BOOK PAGE 126 LINE 19

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1953 9-10-53
CONSERVATION DIVISION
Wichita, Kansas

15-163-02389-00-00

BARNETT OIL COMPANY
LOG OF VEHIGE WELL NO. 1
NW 1/4 NE 1/4 NW 1/4 SECTION 6-6S-20W
ROOKS COUNTY, KANSAS

DATE COMMENCED: August 21, 1953

DATE COMPLETED: August 31, 1953

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	82	
Sand and Sandy Shale	82	105	
Shale and Shells	105	155	Set 8 5/8", 2 1/2" surface pipe at 155 feet; cemented with 125 sacks of cement.
Shale and Sand	155	895	
Shale and Shells	895	1150	
Sand	1150	1370	
Shale - Red	1370	1635	
Anhydrite	1635	1667	
Shale	1667	1834	
Shale and Shells	1834	2260	
Shale	2260	2377	
Lime	2377	2775	
Shale and Lime	2775	3230	
Lime	3230	3490	
Shale and Lime	3490	3539	
Sand	3539	3542	
Total Depth		3542	Dry and Abandoned.

CONFIDENTIAL DIVISION
STATE OF KANSAS

9-10-53

PLUGGING
FILE SEC 6-T-6-R-20W
BOOK PAGE 126 LINE 19