

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: J.D. Production
Address: P.O. Box 309 Geneseo, Kansas 67444
Phone: (620) 824-6156 Operator License #: 8917
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. 3218'

API Number: 15-159-01765-00-00
Lease Name: Meyer
Well Number: 12
Spot Location (QQQQ): _____ - SW - SW - SW
330 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 30 Twp. 18 S. R. 7 East West
County: Rice
Date Well Completed: _____
Plugging Commenced: 12-27-04
Plugging Completed: 12-29-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	310'	None
				5-1/2"	3216'	750'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off with sand to 3000' and 5 sacks cement. Went in to cut casing, pipe parted @750'. Pulled 1 jt. to 720', pumped 30 bbls. water with 100 lbs. hulls, 50 sacks cement and 250# hulls, pulled casing up to 360', pumped 110 sacks cement w/100# hulls and circulated. Layed rest of casing down and topped off with 30 sacks cement & 100# hulls, 60/40 pos, 4% gel. Plugging complete

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: J.D. Production

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 9th day of February, 2005

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 11 2005
KCC WICHITA