

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163,21280 -00-00

LEASE NAME Hansen Foundation

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

3,960 Ft. from S Section Line

4,550 Ft. from E Section Line

SEC. 12 TWP. 6 RGE. 20 ~~XXX~~(W)

COUNTY Rooks

Date Well Completed 05-05-81

Plugging Commenced 12-16-92

Plugging Completed 12-16-92

LEASE OPERATOR K & E Drilling, Inc.

ADDRESS 100 S. Main, Suite 300, Wichita, KS 67202

PHONE# (316) 264-4301 OPERATORS LICENSE NO. 5266

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 11, 1992 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Reagan Depth to Top 3602' Bottom 3607' T.D. 3607'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	285.58'	None
				4-1/2"	3605'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Perforated 4 1/2" @1030' and 1740'. Ran tubing to 2450' & spot 75 sxs cement; spot 85 sxs @1450' and 4 1/2" full of cement. Lay down tubing and squeeze 4 1/2" w/95 sxs cement, pressured to 500#. Pump 100 sxs cement down 8 5/8"x4 1/2" annulus and shut-in w/500# pressure. Pressured 4 1/2" to 700# and shut-in. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. None

Address P.O. Box 628, Great Bend, Kansas 67530

APPROVED  
12-31-92  
DEC 9 1 1992

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: K & E Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Wayne L. Brinegar, Vice President/Production

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wayne L. Brinegar Wayne L. Brinegar  
Vice President

(Address) 100 S. Main, Suite 300, Wichita, KS 67202



AND SWORN TO before me this 18th day of December, 19 92

(Signature) Patricia A. Clarke  
Notary Public

My Commission Expires: August 11, 1995