

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-163-21,137-00-00

LEASE NAME Gartrell

WELL NUMBER A #1

2280 Ft. from <sup>N</sup> Section Line

550 Ft. from <sup>W</sup> Section Line

SEC. 12 TWP. 6 RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 9/80

Plugging Commenced 10/1/01

Plugging Completed 10/1/01

RECEIVED  
11-7-2001  
NOV 07 2001

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR Shelby Resources LLC

ADDRESS 5893 Saddle Creel Trail, Parker, Co 80134

PHONE (303) 840-2183 OPERATORS LICENSE NO. 31725

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/28/01 (date)

by Herb Dienes (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? KCC has copy

Producing Formation LKC Depth to Top 3331' Bottom 3509' T.D. 3594'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil & Water	Surface	303	8 5/8"	9/80	N/A
		"	3590	4 1/2"	9/80	N/A

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from     feet to     feet each set  
SEE ATTACHED

Name of Plugging Contractor Allied Cementing Co. License No. None required

Address Russell, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shelby Resources LLC

STATE OF Kansas COUNTY OF Rooks, ss.

Jim Waechter (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Jim Waechter

(Address) 5893 Saddle Creek Trail, Parker Co

SUBSCRIBED AND SWORN TO before me this 4th day of November, 2001

Brian Karlin  
Notary Public

My Commission Expires: 8-27-05



OR

RECEIVED

NOV 07 2001

KCC WICHITA

**Shelby Resources L.L.C.**

**Gartrell "A" #1**

**C-S/2/SW/NW Sec. 12-6s-20w**

**Rooks County, Ks.**

10-01-01      MIRU Fischer well service and run 2.3/8" tubing to 1725'. Circulate 135 sx 60/40/10 cement to surface. Pull tubing out of the hole and hook on to the 4.1/2" casing. Open the annulus and circulate 40 sx 60/40/10 cement to surface, close surface pipe and pump another 90 sx cement @ 150#. Shut in well. RDMO.