

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-21,184-0000

LEASE NAME WALLGREN "A"

TYPE OR PRINT

WELL NUMBER 1

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Line
4290

2970-330 Ft. from E Section Line

LEASE OPERATOR Petroleum Management, Inc.

SEC. 6 TWP. 6S RGE. 20 (E) or (W)

ADDRESS 14201 East Central, Wichita, KS 67230

COUNTY Rooks

PHONE#(316) 733-5600 OPERATORS LICENSE NO. 5242

Date Well Completed 12-28-80

Character of Well Oil

Plugging Commenced 11-17-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-17-94

The plugging proposal was approved on 11-17-94 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Toronto Depth to Top 3226 Bottom 3230 T.D. 3485

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
KANSAS CORPORATION COMMISSION
12-13-94

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	220'	None
				4 1/2	3484'	None

DEC 13 1994

CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Perf 1620' & 1000'. Ran 2" tubing to 1800'. Spot 100 sxs cement with 100# hulls. Cement circulated to surface, hooked up to 4 1/2" casing & squeezed 100 sxs cement with 200# hulls into well at 500# max psi. Shutin at 200#. 8 5/8" backside squeezed 50 sxs cement with 200# hulls @ 500# max psi. Shutin at 300#.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

R. D. Reber (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 14201 E. Central, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 12th day of December, 19 94

KATHLEEN L. CARTER
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 4-29-95

[Signature]
Notary Public

Commission Expires: _____