

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22649-00-00
Spot: CS2SWSW Sec/Twnshp/Rge: 16-6S-20W
330 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: GEYER Well Number: 2
County: ROOKS Total Vertical Depth: 3750 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

Conductor Pipe: Size feet: \$121.88
Surface Casing: Size 8.625 feet: 268
Production: Size 4.5 feet: 3742
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/10/2002 10:45 AM
Plug Co. License No.: 8925 Plug Co. Name: LIBERTY OPER & COMPL, INC
Proposal Rcvd. from: CHARLEY FARR Company: LIBERTY OPER & COMPL, INC Phone: (785) 434-4686

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 10% gel and hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 06/10/2002 11:15 AM KCC Agent: HERB DEINES

Actual Plugging Report:

8 5/8" to 268' w/15 sxs. 4 1/2" to 3742' w/150 sxs.
D.V. at 1835' to surface. Bad spot at 2200'. Low fluid level.
Tied onto production casing and pumped 220 sxs cement with hulls.
Max. P.S.I. 1500#. S.I.P. 700#.
Tied onto annulus and pumped 5 sxs cement and pressured up.


RECEIVED
JUN 17 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed


(TECHNICIAN)

JUN 13 2002

INVOICED
DATE: 6-18-02
INV. NO. 2002061979

Form CP-2/3

LIBERTY OPERATIONS &
 COMPLETIONS, INC.
 308 WEST MILL

REPLACEMENT CARD

16-6-20W
 C S/2 SW SW


PLAINVILLE, KS. 67663
 CONTR PIONEER DRILLING CO.

#2 GEYER

CTY ROOKS

GEOL KEVIN ADAMS

FIELD TODD NE



ELV 2231 KB SPD 3/26/85 CARD ISSUED 5/16/85 IP P 35 BO & 10 BWPD
2226 GL DRLG COMP 4/3/85 ARB 3711-3718
 API 15-163-22,649

LOG	Tops	Depth/Datum
ANH	1833+	398
TOP	3244	1013
HEEB	3440	1209
TOR	3461	1230
LANS	3473	1242
BKC	3672	1441
ARB	3708	1477
PBTD	3719	1488
RTD	3750	1519

8 5/8 " 268 / 210 SX, 4 1/2 " 3742.52 / 150 SX, MULTI STAGE
 COLLAR AT 1750'
 NO CORES
 DST (1) 3665-3725 (PENN, ARB) / 60-60-60-60, 270' GIP, REC
 240' MCO, SIP 874-823#, FP 94-117 / 134-151#
 MICT - CO, PF (ARB) 3711-3718, W / 4 SPF, AC 250 GAL (15%
 MUD), RE-AC 250 GAL (15% INS, 5% CHECKER SOL), RE-AC 500
 GAL (15% INS), RE-AC 1000 GAL (15% INS), RE-AC 1500 GAL
 (AOG-200), SWB DWN, SO, SET 2 3/8 " TBG AT 3718, POP, P
 35 BO & 10 BWPD, 4/23/85

INFO RELEASED: 9/4/86 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS