

6 061862
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-15
API NUMBER 15- 163-22,510-00-00
SW, SEC. 18, T 6 S, R 20 W/E
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140
Operator: Frontier Oil Co.
Name & Address: 125 N. Market
Suite 1720
Wichita, Ks. 67202

Lease Name McClurg Well # 1
County Rooks 125.13
Well Total Depth 3850 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 204

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050
Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 10:00AM Day: 15 Month: May Year: 19 89

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 300 sks 60/40 Poz 8% Gel 3% Cal Cl 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1989 6-6-89

CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00 PM Day: 15 Month: May Year: 19 89


ACTUAL PLUGGING REPORT 8 5/8" set at 204' w/cwc. 4 1/2" set at 3848' w/150 sks.

Top perf at 3528'. Plugged bottom w/sand and 4 sks cement to 3475'. Shot pipe three times and recovered 2535'. Shot pipe at 2535' and pulled to 1700'. Spotted 125 sks cement. Pulled casing to 900' and circulated cement to surface. Pulled casing and pumped down 8 5/8" filled to surface w/300 sks cement w/700 psi.

Remarks: By Allied
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and ~~do not~~) serve this plugging.

DATE 6-7-89
INV. NO. 25007

Signed 
(TECHNICIAN)
Gilbert G. Scheck