

2-24

6 031500

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,144 -00-00

SW NW SE, SEC. 22, T 6 S, R 20 W/EX

1650 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Chapman Well # 5

Operator: Ritchie Exploration Inc.

County Rooks 71.27

Name & Address 125 N. Market Sutie 1000

Well Total Depth 2193 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 234

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated Problem in hole w/equipment, Plugged

Plugging Contractor Red Tiger License Number

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 24 Month: Feb. Year: 19 91

Plugging proposal received from Lloyd Dellett

(company name) Red Tiger (phone)

were: 8 5/8 set at 234 w/160 sks cwc. Drilled to 2193 8 5/8 parted from 120 to 127 in the middle of string. The bit was hung up at 1525 in cedar hills.

The drill pipe had a twist off point at 214. Order 400 sks 65/35 poz 10% gel w/1/4 lb. flow cele/sk and 1000 lbs. hulls. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 5:45PM Day: 24 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT Pump through drill pipe at 1525 w/250 sks cement blend w/500 lbs. hulls mixed into 300 psi. Back off drill pipe at 214 and circ cement to surf. Hook onto 8 5/8 and sq w/125 sks cement blend w/400 lbs. hulls to hold positive psi 100 lbs. Plug complete.

RECEIVED STATE CORPORATION COMMISSION 3-13-91 MAR 13 1991

Remarks: Anhy 1778 - 1810 Elev. 2177

INVOICED

(If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION Wichita, Kansas

DATE 3-15-91

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 31194

Feb. 5.