

4-032165

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

7-25

API Number: 15-163-22,708

00-00

NE NE NE /4 SEC. 20, 06, 20 W
4950 feet from S section line
330 feet from E section line

Operator license# 8925

Lease: States Well # 1

Operator: Liberty Operations & Completions

County: Rooks

Address: 308 West Mill Street
Plainville, Kansas 67663

Well total depth 3750 121.87 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 257 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 25 Month: July Year: 1996

Plugging proposal received from: Charles Farr

Company: Liberty Operations & Completions, Inc. Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 600# hulls.
Order work string tubing.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 01 1996

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

8-1-96

Completed: Hour: 12:00 P.M., Day: 25, Month: July, Year: 1996

Actual plugging report: 8 5/8" set at 257' cwc with 250 sxs. 4 1/2" set at 3741' with 175 sxs. D.V. Tool at 1772' cwc 300 sxs. Prod. Perfs. - 3691' - 3704'. PBTD 3729'. Ran tubing to fish at 3025' spotted 75 sxs cement blend with 300# hulls. Pulled tubing to 1500'. Spotted and filled hole with 75 sxs cement blend with 300# hulls. Pulled tubing. Squeezed 4 1/2" with 50 sxs cement blend to Max. P.S.I. 500#. Held. 8 5/8" annulus full of cement.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did[] / did not[X] observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE AUG 07 1996
INV. NO. 46198

Form CP-2/3