

6010289

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-22625-00-00

SE, SEC. 19, T. 6 S, R. 20 W  
990 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Wyrill Well # A-1

Operator: Frontier Oil Co.

County Rooks 122.04

Name & Address 1720 K.S. B. Bldg.

Well Total Depth 3755 feet

Wichita KS

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 222 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 3 AM Day: 9 Month: 2 Year: 19 85

Plugging proposal received from Walt Oden

(company name) Red Tiger (phone) \_\_\_\_\_

were: order 210 sx. cem. 50/50 portmix 6% gel. 3% c.c.

1. 8 5/8 plug 1. 5x hulls 1. 5x flow seal.

Heavy mud between all plugs.

Pump cement down drill pipe

Elev- 2262 Anhydrite-1873-1903 Arbuckle. 3747

Dakota-1400 Plugging Proposal Received by Dale Batthazor (TECHNICIAN)  
862 = 1160

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 8:45 AM Day: 9 Month: 2 Year: 19 85

ACTUAL PLUGGING REPORT circ @ 3740 for 30 mi.

25 sx @ 3740

25 sx @ 1890

100 sx @ 1160 w/ 1 sx. flow seal.

40 sx @ 250

10 sx @ 40 on solid bridge

Remarks: 10 sx in Rat Hole cem. co. Allied  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging

DATE 2-19-85

INV. NO. 7031

Signed Dale Batthazor (TECHNICIAN)

2-15-85  
RECEIVED  
STATE CORPORATION COMMISSION  
FEB 15 1985  
CONSERVATION DIVISION  
Wichita, Kansas

⓪

2-15-85  
9