

4 060044

12-18

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,071-00-00  
50'S  
W2 W2 SW, SEC. 23, T 6 S, R 20 ~~W~~ ~~E~~ ~~X~~

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Operator: Mid-Continent Energy Corp.  
Name & Address 155 N. Market, Suite 200  
Wichita, KS 67202

1270 feet from S section line  
4950 feet from E section line

Lease Name Weber Well # 1

County Rooks 120.25

Well Total Depth 3700 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXXXXXXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Lloyd Drilling License Number 3300

Address Morland, KS

Company to plug at: Hour: 3:15PM Day: 18 Month: December Year: 19 89

Plugging proposal received from Lloyd Pfeifer

(company name) Lloyd Drilling (phone) 913-627-5871

were: Space all plugs with heavy drilling mud through drill pipe  
Order 200 sxs. of 60/40 pos 6% gel 1/4# floccel per sx.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXXXX

Operations Completed: Hour: 3:15PM Day: 18 Month: December Year: 19 89

ACTUAL PLUGGING REPORT 1 st plug at 1790' with 25 sxs. Anhydrite 1763-1803'

2 nd plug at 1065' with 100 sxs. Dakota 763-1063'

3 rd plug at 280' with 40 sxs. Surface pipe to 228'

4th plug at 40' with 10 sxs. wiper plug at 40'

rathole with 15 sxs. mouse hole with 10 sxs.

Arbuckle not reached

Remarks: B-J Titan

(If additional description is necessary, use BACK of this form.)

~~(XXXX)~~ I did not observe this plugging.

**INVOICED**

DATE JAN 24 1990

INV. NO. 27132

Signed Herb Deines  
(TECHNICIAN)  
Herb Deines

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 17 1990  
1-17-90  
CONSERVATION DIVISION  
Wichita, Kansas