

To: **6 050015**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-1 API NUMBER 15- 163-23,020-00-00 **385**

W/2 W/2 NE, SEC. 23, T. 6 S, R 20 W/E

3960 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6926

Lease Name Greg Gartrell Well # 1

Operator: Advantage Resources Inc.
Name & Address 1775 Sherman St.
Suite 1375
Denver, Co 80203

County Rooks **120.35**
Well Total Depth 3,703 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling License Number

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 4 Month: Oct. Year: 19 88

Plugging proposal received from Pat Watner

(company name) Red Tiger (phone)

were: Order 190 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1988
11-8-88

Plugging Proposal Received by Bruce D. Basye

(TECHNICIAN)

Plugging Operations headed by Agent?: All Part None X

Operations Completed: Hour: 6:30PM Day: 4 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT

1st plug at 1850' w/25 sks Anhydrite

2nd plug 1080' w/100 sks 1 sk F.C. Dakota

3rd plug at 320' w/40 sks

4th plug at 40' w/10 sks

15 sks in rathole.

Remarks: Allied Russell

(If additional description is necessary, use BACK of this form.)

INVOICED
(If ~~you~~ do not observe this plugging.

DATE 11-9-88

INV. NO. 22938

Signed Bruce D. Basye
(TECHNICIAN)

Bruce D. Basye