

11-14

0000

To: **6 041254**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,127  
NE SW SW, SEC. 22, T 6 S, R 20 W/E

990 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

Lease Name Gartrell Well # 4

Operator: Baird Oil Company

County Rooks 119.53

Name & Address Box 428

Well Total Depth 3678 feet

Logan, Ks. 67646

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 242 w/170 sk

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling Inc. License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Harold Maley

(company name) Abercrombie Inc. (phone) \_\_\_\_\_

were: Order 215 sks cement 60/40 poz 6% gel and 1/2 per sk f.c.

Heavy mud between all plugs.

Pump cement down drill pipe.

elevation 2143 Anhy 1750-78

Top Dakota 1400 Plugging Proposal Received by Dennis Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part xx None \_\_\_\_\_

Operations Completed: Hour: 4:00 PM Day: 14 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT 25 sks at 3673

25 sks at 1775

100 sks at 1040

40 sks at 270

10 sks at 40

15 sks in rathole.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1990  
11-30-90  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: lots ck'd by HD  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

(do not observe this plugging.)

DATE 12-6-90

INV. NO. 30159

*J.S.*

Signed Dennis Hamel  
(TECHNICIAN)

Dennis Hamel