

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-10361-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 6-21S-11W  
1550 feet from S Section Line, 1728 feet from E Section Line  
Lease Name: VEEDER DIETZ Well #: 2  
County: STAFFORD Total Vertical Depth: 3479 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

PROD Size: 5.5 feet: 3445 WITH 125 SX CMT  
SURF Size: 8.625 feet: 325

# 113<sup>07</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/21/2005 10:30 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: STAN FROESTNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: SAND BACK TO 3390' & 5 SX CMT. CIRCULATE CMT FROM 480' TO SURFACE DOWN 5 1/2" & UP 5 1/2"/8 5/8" ANNULUS. SHUT BACKSIDE IN & SQUEEZE IN ANOTHER 100 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER  
Date/Time Plugging Completed: 02/21/2005 2:45 PM

WitnessType: COMPLETE (100%)  
KCC Agent: RICHARD LACEY

Actual Plugging Report:

TOC =2950'. ANHYDRITE @ 500'. HOLES IN 5 1/2" CASING @ 480'. SANDED TO 3426'. RAN TUBING TO 3400' & PUMPED 30 SX CMT & DISPLACED. PUMPED DOWN 5 1/2" WITH 130 SX CMT CIRCULATING CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS. CLOSED IN ANNULUS & PUMPED 80 SX CMT DOWN 5 1/2". MAXIMUM PRESSURE 200 PSIG. SHUT IN PRESSURE 100 PSIG.

Perfs:

Top	Bot	Thru	Comments
3445	3478	OH	
3240	3438		

RECEIVED  
FEB 25 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
FEB 22 2005  
KCC Dodge City

Signed

Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 2-25-05  
WWW.NOR 2005061224

Form CP-2/3