

4 060122

10-12

124 P

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SW SE SW  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,119-00-00  
SEC. 22, T 6 S, R 20 W/E

330 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

Lease Name Gartrell Well # 3

Operator: Baird Oil Company

County Books 120.15

Name & Address P.O. Box 428

Well Total Depth 3697 feet

Logan, KS 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXXXX

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling Co. License Number 5422

Address Wichita, KS

Company to plug at: Hour: 8:30AM Day: 12 Month: October Year: 19 90

Plugging proposal received from Lloyd Delett

(company name) Abercrombie Drilling Co. (phone)

were: Order 215 sxs. 60/40 pos 6% gel 1/4# floccel per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XXXXXXXX

Operations Completed: Hour: 8:30AM Day: 12 Month: October Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3665' with 25 sxs. Arbuckle at 3675'

2nd plug at 1770' with 25 sxs. Anhydrite 1758-1790'

3rd plug at 1060' with 100 sxs. Dakota 757-1057'

4th plug at 300' with 40 sxs. Surface pipe to 246'

5th plug at 40' with 10 sxs. 16-25-90

rathole with 15 sxs.

Remarks: Halliburton Cementing

INVOICED

If additional description is necessary, use BACK of this form.

I ~~XXXXX~~ did not observe this plugging.

DATE 10-20-90

INV. NO. 29785

Handwritten initials

Signed [Signature] (TECHNICIAN)

Herb Deines