

3-24-88

312

6070657

API NUMBER 15- 163-22,988-000-00R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SE, SEC. 22, T 6 S, R 20 (W)

2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Chapman Well # 3

Operator: Ritchie Exploration Inc.
Name & Address: 125 N. Market #1000
Wichita, Ks. 67202
Jeff Christian

County Rooks 119.70
Well Total Depth 3683 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling License Number _____

Address 1720 Ks. State Bank Bldg. Wichita, Ks. 67202

Company to plug at: Hour: 9:00AM Day: 23 Month: March Year: 19 88

Plugging proposal received from Mike Waggoner

(company name) Red Tiger Drilling Inc. (phone) _____

were: 8 5/8" -261' S.P. cwc w/150 sks 60/40 Poz 2% Gel 3% Ca Cl. By Allied

Arbuckle at 3650'. Elevation 2167' Anhy 1763' Mud condition. 96 weight; 45 viscosity;

10.6 water loss. No circulation problems. Proposal 225 sks 60/40 Pozmix 6% Gel 3% Ca Cl

1 sk Celloflake and 8 5/8" plug. Spot with drill stem, circulate mud between plugs.

25 sks at 3625'; 25 sks at 1775'; 100 sks Celloflake at 1060'. 50 sks at 300'. 10 sks at 40'. 15 sks in rathole. (circulate)

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:30AM Day: 24 Month: March Year: 19 88

ACTUAL PLUGGING REPORT Ordered 225 sks 60/40 Pozmix 6% Gel 3% Ca Cl. 1 sk

Celloflake and 8 5/8" plug. Circulated hole. Spotted with drill stem. Heavy mud

between all plugs. 1st plug at 3625' w/25 sks 2nd plug at 1775' w/25 sks cement.

3rd plug at 1060' w/100 sks w/1 sk Flocele. 4th plug at 300' w/50 sks cement.

5th plug Hulls. Plug at 40' w/10 sks cement. 15 sks rathole (circulate).

RECEIVED STATE CORPORATION COMMISSION

Remarks: Cemented by Allied Cementing (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-22-88

INV. NO. 20940

CONSERVATION DIVISION Wichita, Kansas

Marion J. Schmidt (TECHNICIAN)