

6 070390

API NUMBER 15-163-22, 743-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5/2-SW-NE SEC. 22, T. 6 S. R. 20

2970 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name VOSE Well # 1

Operator: H. Scott Ritchie

County ROOKS 119.28

Name & Address 125 N. Market, # 950

Well Total Depth 3670 feet

Wichita, Kans

Conductor Pipe: Size 0 feet

67202

Surface Casing: Size 8 5/8 feet 219

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co License Number \_\_\_\_\_

Address Wichita, Kans, 67202

Company to plug at: Hour: 3:00 AM Day: 10<sup>th</sup> Month: Sept Year: 19 85

Plugging proposal received from most Shertich tag # 608

(company name) Murfin Drilling Inc (phone) 6023

were: 8 5/8" - 219<sup>ft</sup> SR. cu. w/ 165<sup>SK</sup> Common Gel - Ca. Cl. (By Allied Int)

Order 210<sup>SK</sup> 60/40 Pozmix Gel - Ca. Cl. - 1<sup>SK</sup> x Cello and 8 5/8" Plug

Spot with Drill Stem Recondition Hole (viscosity) Heavy Mud Between All Plugs

Embarkle Well, ELV. 2176, Empty 1779, No circulation problems

Mud Condition 48 Viscosity - 9.6 weight, 8.8 Water Log.

Plugging Proposal Received by Marion Schmidt  
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 8:30 AM Day: 11<sup>th</sup> Month: Sept Year: 19 85

ACTUAL PLUGGING REPORT Ordered 210<sup>SK</sup> 60/40 Pozmix 6% Gel 3% Ca. - 1<sup>SK</sup> x Cello and 8 5/8" Plug

Spot with Drill Stem Recondition Hole, Heavy Mud Between All Plugs

1<sup>st</sup> Plug @ 3630' w/ 25<sup>SK</sup> ent, 2<sup>nd</sup> Plug @ 1800<sup>ft</sup> w/ 25<sup>SK</sup> ent

3<sup>rd</sup> Plug @ 1070<sup>ft</sup> w/ 100<sup>SK</sup> ent + 1<sup>SK</sup> Cello Stake, 4<sup>th</sup> Plug @ 240<sup>ft</sup> w/ 40<sup>SK</sup> ent

5<sup>th</sup> Plug Solid Bridge @ 40<sup>ft</sup> w/ 10<sup>SK</sup> ent (Circulab) 10' in Mouse

Hole (Circulab) Cemented by Allied Int.

Remarks: \_\_\_\_\_ (If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 25 1985

INV. NO. 10258 OCT 09 1985

Signed Marion Schmidt  
DOIC (TECHNICIAN)