

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19482-00-01
Spot: SWSENE Sec/Twnshp/Rge: 31-23S-5E
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: CLEARWATER Well #: 11
County: BUTLER Total Vertical Depth: 2458 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 2441
SURF Size: 8.625 feet: 80

Well Type: EOR UIC Docket No: E16357.2 Date/Time to Plug: 12/28/2004 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2004 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Perfs:

Ran 2" tubing to 2350' and pumped 35 sacks of cement.
Pulled tubing to 1800' and let set for 1-1/2 hours.
Ran tubing back to 2180' and tagged top of cement.
Pulled tubing to 280' and circulated cement to surface with 33 sacks of cement.

United #6033

60/40 posmix with 4% gel

RECEIVED
KCC DISTRICT #2
FEB 7 - 2005
WICHITA, KS

RECEIVED
FEB 24 2005
KCC WICHITA

Remarks: CONTROL #2004-0042-002

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

cc D. WERZ
B. JENKINS