

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-19016-00-00
Spot: NESENE Sec/Twnshp/Rge: 24-18S-8W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: PICKERILL Well #: 3
County: RICE Total Vertical Depth: 3180 feet

Operator License No.: 31389
Op Name: NOBLE PETROLEUM, INC.
Address: 3101 N. ROCK ROAD, STE 125
WICHITA, KS 67226

PROD Size: 7 feet: 3127
SURF Size: 10.75 feet: 223

#103³⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2005 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: NOTE: NOBLE PURCHASED FROM DEAN GUSTUS 11-1-2004. THIS HOLE WAS ABD. AT TIME OF PURCHASE. NOBLE HAS NOT TOUCHED THIS HOLE SINCE PURCHASING. POOR RECORDS AVAILABLE.
Set CIBP @ 2775'; set 3 sxs on top; perf @ 1050', 700', 275'; Pump 50 sxs @ 1050', 50 sxs @ 700'; pull tubing to 275'; and circ to surf.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 01/19/2005 4:30 PM KCC Agent: GREG EVES

Actual Plugging Report:

Set CIBP at 2775' and set 3 sacks of cement on top. Perforated pipe at 1050', 700', and 275'. Pumped 50 sacks of cement at 1050' and 700'. Pumped 100 sacks of cement at 275' to circulate to surface. Pulled tubing and topped off with another 10 sacks of cement.

Copeland Cementing #25758

210 sacks of 60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3127	3180		
2828	2832		

RECEIVED
KCC DISTRICT #2

JAN 26 2005

WICHITA, KS

RECEIVED
FEB 24 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Greg Eves
(TECHNICIAN)

INVOICED
DATE 2.25.05
2005061225