

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00696-00-00
Spot: S2NWSE Sec/Twnshp/Rge: 28-16S-10W
1650 feet from S Section Line, 1980 feet from E Section Line
Lease Name: LOULA A Well #: 5
County: ELLSWORTH Total Vertical Depth: 3289 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3281
SURF Size: 8.625 feet: 343 200

#106⁸⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/14/2005 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: RICK POPP Company: EXPRESS WELL SERVICE & SUPPL Phone: (620) 786-5514

Proposed Plugging Method: Sand open hole to 3230' and put 5 sacks of cement on top. Perforate at 1350', 1000', 650', and 400'. Run tubing to 1350' and pump 35 sacks of cement. Pull tubing to 1000' and pump 35 sacks of cement. Pull tubing to 650' and pump 35 sacks of cement. Pull tubing to 400' and circulate cement to surface.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/15/2005 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded open hole to 3230' and put 5 sacks cement on top. Perforated at 1350', 1000', 650', and 400'. Ran tubing to 1350' and pumped 35 sacks of cement. Pulled tubing to 1000' and pumped 35 sacks of cement. Pull tubing to 650' and pumped 35 sacks of cement. Pulled tubing to 400' and attempted to circulate cement to surface. Did not get circulation on 2/14/2005. Ran tubing down to 1350' on 2/15/2005 and repeated same procedure as day before, but with cotton hulls and calcium chloride. Did get circulation on both 5-1/2" and 8-5/8".

Perfs:

Top	Bot	Thru	Comments
3281	3289		
RECEIVED KCC DISTRICT #2 FEB 18 2005 WICHITA, KS			
RECEIVED FEB 24 2005			

Remarks:

Plugged through: TBG

KCC WICHITA

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 2-25-05
*INVOICE NO. 2005061223