

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22007-00-00  
Spot: SWNWSWNE Sec/Twnshp/Rge: 2-25S-5E  
3464 feet from S Section Line, 2578 feet from E Section Line  
Lease Name: ALTHOUSE Well #: 1  
County: BUTLER Total Vertical Depth: 2554 feet

Operator License No.: 102

CIBP Size: feet: 2350

Op Name: KDOT

PROD Size: 5.5 feet: 2551

Address:

SURF Size: 8.625 feet: 217 UNKNOWN

KS

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/13/2004 8:00 AM

Plug Co. License No.: 3097

Plug Co. Name: K W OIL WELL SERVICE. INC.

Proposal Rcvd. from: JIM KEPLEY

Company: K W OIL WELL SERVICE. INC.

Phone: (620) 431-2285

Proposed  
Plugging  
Method:

SET BRIDGE PLUG @ 2350', 3 SX CMT ON TOP OF PLUG, PERF 5-1/2 @ 300' COM LITE CMT TO TOP IN AND OUTSIDE OF 5-1/2.

Plugging Proposal Received By: DAVE WERTZ

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/14/2004 12:00 AM

KCC Agent: DAVE WERTZ

Actual Plugging Report:

Perfs:

10/13/2004 -- Set CIBP at 2350' and capped with 3 sacks of cement. Perforated at 300'. Ran 1" to 300' and pumped 125 sacks of cement. Did not circulate.

10/14/2005 -- Loaded hole and ran 1" to 300'. Pumped 140 sacks of cement with 200 lbs of cotton hulls. Cement circulated.

W W Production did cementing

60/40 posmix with 4% gel

Top	Bot	Thru	Comments
-----	-----	------	----------

300

RECEIVED  
KCC DISTRICT #2

FEB 22 2005

WICHITA, KS

RECEIVED

FEB 24 2005

KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

David Wertz

(TECHNICIAN)