

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21423-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 2-25S-5E  
2408 feet from S Section Line, 2606 feet from E Section Line  
Lease Name: DELLETTE Well #: 1  
County: BUTLER Total Vertical Depth: 2660 feet

Operator License No.: 102

Op Name: KDOT

Address:

KS

CIBP Size: feet: 1780

PROD Size: 4.5 feet: 2660 200 SX CMT

SURF Size: 8.625 feet: 0 UNKNOWN

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/13/2004 8:00 AM

Plug Co. License No.: 3097

Plug Co. Name: K W OIL WELL SERVICE, INC.

Proposal Rcvd. from: JIM KEPLEY

Company: K W OIL WELL SERVICE, INC.

Phone: (620) 431-2285

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/13/2004 5:00 PM

KCC Agent: DAVE WERTZ

Actual Plugging Report:

Perfs:

Set bridge plug at 1780' with 3 sacks of cement on top. Perforated 4-1/2" casing at 300'. Ran 1" on inside of the 4-1/2" to 300' and circulated cement to surface. Pulled and ran 1" on outside of the 4-1/2" to 300' and circulated cement to surface.

Total cement -- 140 sacks

60/40 posmix with 4% gel

Top	Bot	Thru	Comments
300			
<b>RECEIVED KCC DISTRICT #2 FEB 7 - 2005 WICHITA, KS</b>			
<b>RECEIVED FEB 24 2005 KCC WICHITA</b>			

Remarks:

Plugged through: TBG

District: 02

Signed

*David Wertz*

(TECHNICIAN)