

4-041715

8-30

API Number: 15-163-21,868-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SW SW NE /4 SEC. 26, 06 S, 20 W  
2970 feet from S section line  
2310 feet from E section line

Operator license# 6278

Lease: Gartrell Well # 4

Operator: Anchor Bay Corporation

County: Rooks 118.46

Address: 1600 Stout Street  
Suite 1400  
Denver, CO 80202

Well total depth 3645 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 254 feet  
W/165 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 30 Month: August Year 1995

Plugging proposal received from: W.J. Luck

Company: Anchor Bay Corporation Phone:

Were: 4 1/2" casing set at 3643' w/175 sxs cement. Perf. At 3308' - 3310'.  
Perf anhy at 1700' - Dakota at 1000' - W.L.M. at 3400' - T.O.F. at 1700'  
Ordered 225 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

RECEIVED  
CORPORATION COMMISSION  
SEP 15 1995  
9-15-95  
CORPORATION COMMISSION

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 2:00 P.M., Day: 30, Month: August, Year: 1995

Actual plugging report: R.U. cementers to 4 1/2" casing - pumped down casing - 25 sxs cement with 200# hulls, followed with 7 sxs gel, followed with 150 sxs cement with 200# hulls. Max. P.S.I. 600#. S.I.P. 300#. 8 5/8" S.P. Found hole in surface pipe at ground level - released P.S.I. from 4 1/2" casing. R.I.H. with perf to 250' - perforated casing. R.U. cementers to 4 1/2" casing and circulated cement to surface in annulus with 50 sxs cement. Job completed.

Remarks:  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES, CALC X, NO  
Plugged through TUBING, CASING X. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED

DATE 9-21-95  
INV. NO. 43556