

6-050160

8-1

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-21615-00-01

SW SW NE /4 SEC. 26, 6 S, 20 W  
2970 feet from S section line  
2310 feet from E section line

Operator license# 6278

Lease Gartrell well # 2

Operator: Anchor Bay

County Rooks

Address: 1600 Stout Street  
# 1400  
Denver, Colorado

Well total depth 3705 feet <sup>120.41</sup>  
Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 169 feet

Aband. oil well       , Gas well       , Input well EOR, SWD        D & A       

Plugging contractor: Express Well Service License# 6426

Address: Victoria, Kansas

Company to plug at: Hour: PM Day: 1 Month: August Year: 1995

Plugging proposal received from: Bill Luck

Company: Anchor Bay phone:       

Were: 4 1/2" casing set at 3700' with 175 sx. Perfs at 3340'-3638'.  
PBT 3624'. Bailer stuck in hole at 1300'. Milled for three days, out of  
hole at 1220'  
Perf at 180' and 945'. Run tubing to plug. Order out 50 sx common, 200 sx  
60/40 poz, 8% gel, 500# hulls

Plugging Proposal Received by: Bruce Basye  
Plugging operations attended by agent? All[XXX], Part[ ], None[ ]

Completed: Hour: 3:00 PM, Day: 1, Month: August, Year: 1995

Actual plugging report: Perfed at 180' and 945'. Ran tubing to 1200'.  
Pumped 50 sx common cement. Pulled tubing to 700'. Pumped 25sx 60/40 poz  
8% gel with hulls followed with 25 sx 60/40 poz 8% gel without hulls.  
Circulated cement. Pulled tubing. Pumped 100 sx 60/40 poz, 8% gel at  
500# down 4 1/2" casing. Pumped 5 sx 60/40 poz down annulus at 500# max.  
Tied back on to 4 1/2" casing and pumped to 500# immediately.

Remarks:         
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO  
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES, NO  
Plugged through TUBING X, CASING Elevation: 2122 GR

I did X did not        observe the plugging.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 07 1995

Bruce Basye  
Bruce D. Basye  
(agent)

Form CP-2/3

**INVOICED**  
DATE 8-15-95  
INV. NO. 43311

*Handwritten initials*