

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,625

LEASE NAME Wyrill "A" 00-00

WELL NUMBER #1

SPOT LOCATION NW SE SE

SEC. 19 TWP. 6S RGE. 20W (E) or (W)

COUNTY Rooks

Date Well Completed 2-9-85

Plugging Commenced 2-9-85

Plugging Completed 2-9-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Frontier Oil Company

ADDRESS 125 N. Market, Ste 1720, Wichita, Ks. 67202

PHONE # (316) 263-1201 OPERATORS LICENSE NO. 5140.

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dale Balthazor, Hays.

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation N/A Depth to top _____ bottom T.D. 3755'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand-Shale, Shale</u>	<u>150sx 60-40 poz</u>	<u>-0-</u>	<u>222'</u>	<u>8-5/8"</u>	<u>215'</u>	<u>-0-</u>
	<u>2% gel 3% cc</u>					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to _____ feet each set.

Plugged @ 3740'/25sx, 1890'/25sx, 1160'/100sx, 250'/40sx, 40'/10sx, 2 sx hulls & plug. Rathole w/10sx. Cemented with 210 sx 50-50 Poz, 6% gel 3% cc. (Plugs calculated by displacement).

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. N/A

Address P O Box 31, Russell, Ks. 67665

STATE OF Kansas COUNTY OF Sedgwick, ss. FEB 27 1985


Jean Angle

(employee of operator) or 2-27-85
I have knowledge of the facts, statements, and matters herein contained and the contents of the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jean Angle

(Address) 125 N. Market, Ste 1720, Wichita.

SUBSCRIBED AND SWORN TO before me this 26 day of February, 19 85



Stella Sewell
Notary Public