

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23-036 *0000*

LEASE NAME Wyrill-19B

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

2970 Ft. from E Section Line

LEASE OPERATOR Ritchie Exploration, Inc.

SEC. 19 TWP. 6 RGE. 20 (E) or (W)

ADDRESS 125 N. Market, Suite 1000, Wichita, KS 67202 COUNTY Rooks

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Date Well Completed 3/89

Character of Well oil

Plugging Commenced 8/1/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/1/91

The plugging proposal was approved on 8/1/91 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation L/KC & Marmaton Depth to Top 3682½' Bottom 3742½' T.D. 3820'

Show depth and thickness of all water, oil and gas formations.

PBTD: 3798'

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/KC	Oil & Water	3530'	3717'	8-5/8"	215'	-0-
Marmaton		3739'	3764'	4½"	3819'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Pumped 225 sx 65/35 pozmix + 10% gel + 500# hulls down 4½" csg. Squeezed to 1000# max psi. Shut-in @ 800#. Cement visible to surface in 8-5/8" csg. Job complete at 9:45 a.m., 8/1/91. Witnessed & approved by Carl Goodrow w/KCC.
Note: Port collar @ 1900' w/400 sx to surface on 3/29/89.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 628, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ritchie Exploration, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, Wichita 67202

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 19 91

Sherrie L. Brooks
Notary Public
Sherrie L. Brooks

Commission Expires: 08-30-94

