

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

LEASE OPERATOR Liberty Operations & Completions, Inc.

SPOT LOCATION - NE - NE - NE

ADDRESS 308 West Mill

SEC. 20 TWP. 6s S. RGE 20w (E) or (W)

CITY, STATE, ZIP Plainville, Kansas 67663

COUNTY Rooks

PHONE#(913) 434-4686 OPERATORS LICENSE NO. 8925

Date Well Completed Sept. 1985

Character of Well Oil  
(oil, gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced July 1996

Date Plugging Completed 7-25-96

The plugging proposal was approved on 7-25-96 (date)

by Herb Dienes Hays, Kansas (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation(s) Arbuckle Depth to Top 3690 Bottom \_\_\_\_\_ T.D. 3750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS D.V. tool @ 1772', Cement Circulated 300 sx.

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Anhydrite	L/S	1815	1846	8-5/8	259'	None
Lime Stone Topeka	L/S	3212	3412	4-1/2	3741'	None
Lsg. K.C.	L/S	3454	3650			
Arb.	Dolomite	3690				

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

300# Hulls.

Sanded in tubing & rods 3725' to 3025'. Ran tubing to 3025 spot 75'sx, pull tubing to 1500' spot & fill hole with 75s x 60/40 Poz. 10% Gel. 300# hulls, pull tubing squeeze down tubing w/50'sx to 500# standing pressure. Annulus full cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co.

License No. \_\_\_\_\_

Address Russell, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Liberty Operations & Completions, Inc.

STATE OF Kansas COUNTY OF Rooks, ss.

Roger L. Comeau (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Roger L. Comeau

(Address) 308 W. Mill

SUBSCRIBED AND SWORN TO before me this 26 day of July, 19 96

My Commission Expires: 9-18-96

Sherry Folsom  
Notary Public

RECEIVED  
KANSAS CORPORATION COMMISSION  
7-29-96  
JUL 29 1996

CONSERVATION DIVISION  
WICHITA, KS

