

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-23,020

LEASE NAME Gregory Gartrell EtAl

WELL NUMBER 1

SPOT LOCATION W/2 W/2 NE/4

SEC. 23 TWP. 6S RGE 20W (E/W) (N/S) (W/E)

COUNTY Rooks

Date Well Completed 10/4/88

Plugging Commenced 10/4/88

Plugging Completed 10/4/88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Advantage Resources, Inc.  
ADDRESS 1775 Sherman St., Suite 1375, Denver, Colorado 80203

PHONE # (303) 831-1912 OPERATORS LICENSE NO. 6926

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks. - Bruce Casey

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3,703'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER PRODUCTION \_\_\_\_\_ CASING RECORD \_\_\_\_\_  
STATE CORPORATION COMMISSION 10-19-88

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 5/8"</u>	<u>263'</u>	<u>-0-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug @ 1850' w/25 sx cement; 2nd Plug @ 1080' w/100 sx cement, 1 sx Flocele;  
3rd Plug @ 320' w/40 sx cement; Bridge Plug @ 40' w/10 sx cement;  
15 sx cement in rathole  
190 sx 60/40 Pozmix, 6% Gel, 3%CC

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Red Tiger Drilling Company License No. 5302  
Address 1720 KSB Building, Wichita, Kansas 67202

STATE OF Colorado COUNTY OF Donner, ss.

Edward G. Ackman (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) 

(Address) 1775 Sherman, #1375

SUBSCRIBED AND SWORN TO before me this 14 day of October, 1988

Mary Anne Oray  
Notary Public

My Commission expires: October 22, 1988