


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail of Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-163-00779-00-00
WELL PLUGGING RECORD



NORTH
Locate well correctly on above
Section Plat

Rooks County. Sec. 23 Twp. 6S Rge. 20W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NE
Lease Owner C-G Drilling Co., N. Appleman Co., &
Lease Name Gartrell Holly Oil Company Well No. 1
Office Address 107 Rule Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 3 19 57
Application for plugging filed January 3 19 57
Application for plugging approved January 3 19 57
Plugging commenced January 3 19 57
Plugging completed January 3 19 57
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3712 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	182.78'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 500'. Set plug. Put in 20 sacks cement. Filled to 175'. Set plug. Put in 1/2 sack hulls and 15 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1958
CONSERVATION DIVISION
WICHITA, KANSAS
1-9-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Bldg.
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January 19 58

My commission expires May 20, 1959
Vicky Jacobs Notary Public.

PLUGGING
FILE SEC 23 T. 6 R. 20W
BOOK PAGE 24 LINE 28

CONTRACTOR'S WELL LOG

OPERATOR C-G Drilling Co., N. Appleman Co., & Holly Oil Company - Gartrell #1

LOCATION SE SE NE SEC. 23-6S-20W RIG NO. 2

COUNTY Rooks STATE Kansas

COMMENCEMENT DATE December 23, 1957 COMPLETION DATE January 3, 1958

LOG OF WELL

Elevation 2167' rotary bushing.
All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	182	Sand-Shale		
182	380	Shale-Sand		
380	1025	Shale		
1025	1250	Shale-Sand		
1250	1808	Shale-Sand		
1808	1820	Shale-Sand		
1820	1839	Anhydrite		
1839	2090	Shale-Shell		
2090	2360	Shale-Shell		
2360	2490	Shale-Shell		
2490	2645	Shale-Lime	0° - 2500	
2645	2820	Shale-Lime	0° - 2750	
2820	2954	Shale-Lime		
2954	3042	Shale-Lime	0° - 3000	
3042	3162	Shale-Lime		
3162	3275	Shale-Lime	0° - 3250	
3275	3342	Lime		
3342	3414	Lime		
3414	3452	Lime		
3452	3477	Lime		DST 3463-3472'
3477	3502	Lime		
3502	3559	Lime		
3559	3600	Lime		
3600	3664	Lime		
3664	3679	Lime		DST 3670-3679'
3679	3700	Arbuckle		
3700	3712	Arbuckle		DST 3700-3712'

CASING LEFT IN HOLE AFTER COMPLETION

Ran 182.78' (9 jts.) 8-5/8" OD Surface Casing.

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

STATE OF KANSAS
1-9-58

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6th day of January, 1958.

Vicky Jacobs
Vicky Jacobs, Notary Public

My commission expires: May 20, 1959

PLUGGING
23 T. 6 R. 20W
BOOK PAGE 44 LINE 35