

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Lotus Operating Co., LLC.
Address: 100 S. Main #420 Wichita, Ks. 67202
Phone: (316) 262-1077 Operator License #: 31980
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. 4823'

API Number: 15-151-21,485-00-00
Lease Name: Bolser RG
Well Number: 3
Spot Location (QQQQ): SE-SW-NW-SW/4
1400 Feet from North / South Section Line
390 Feet from East / West Section Line
Sec. 4 Twp. 29 S. R. 15W East West
County: Pratt
Date Well Completed: _____
Plugging Commenced: 2-8-05
Plugging Completed: 2-9-05

KCC
B.E.M.
2-25-05
R.B.M.S.
CP213

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	432'	None
				5-1/2"	4818'	2540'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 4500' and 5 sacks cement. Cut casing loose @2540', pulled up to 930', pumped 15 sacks gel, 50 sacks cement & 100# hulls, pulled up to 460', pumped 50 sacks cement & 100# hulls, pulled up to 40' and circulated 25 sacks cement, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Lotus Operating Co. LLC.

State of Kansas County, Rice, ss.

RECEIVED

Mike Kelso (Employee of Operator) or (Operator) on above described well being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

FEB 25 2005

KCC WICHITA


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 22nd day of February, 2005

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]