

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-21,615-0001

LEASE NAME Gartrell

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #2

2970 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 26 TWP. 6 RGE. 20 ~~XXX~~ or (W)

COUNTY Rooks

Date Well Completed 5/25/82

Plugging Commenced 8/1/95

Plugging Completed 8/1/95

LEASE OPERATOR Anchor Bay Corporation

ADDRESS 1600 Stout Street #1400 Denver, Colo 80202

PHONE# (303) 629-1098 OPERATORS LICENSE NO. 6278

Character of Well ~~OIL~~ FOR <sup>Kcay</sup>

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/1/95 (date)

by Bruce Basye (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3615' Bottom 3705' T.D. 3705'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	Oil	3336	3352	4 1/2"		NONE
Lansing/Kansas City	Oil	3352	3563	4 1/2 "		NONE
Arbuckle	Oil	3615	3705	4 1/2"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

SEE ATTACHED WORKOVER AND CEMENT TICKETS.

(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION

Name of Plugging Contractor L K Wireline Inc License No. \_\_\_\_\_

Address P O Box 1188 Hays, Kansas 67601

AUG 14 1995

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anchor Bay Corporation

STATE OF Colorado COUNTY OF Denver, ss.

David F Wiesner

(Employee of Operator) or (XXXXXXXX) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David F Wiesner

(Address) 1600 Stout St #1400 Denver, Co 80202

SUBSCRIBED AND SWORN TO before me this 10 day of August, 19 95

Erika E Wilson  
Notary Public

My Commission Expires: 12/10/96

15-165-21615-00-00

W. J. Luck Consultant  
Box 1045  
Great Bend Kansas 67530

RECEIVED  
AUG 1 1995

Mr. David Wiesner  
Anchor Bay Corp.  
1600 Stout St. Suite 1400  
Denver Colorado 80202

Re; Gartrell #-2  
Rooks Couty Kansas

07-28-95

Rigged up Express Well Service, ran bit and tubing to 1220. Mixed mud for three hours. Started drilling, couldn't make any hole. Pulled bit, ran open end tubing back in well still couldn't any hole, pulled tubing, ran bit back drilled for two hours. Pulled tubing and bit, shut down for week end.

07-31-95

Ran joint of wasd pipe and mill shoe, milled from 1220 to 1245. Pulled mill had 5 feet of the bailer in wash pipe. Ran mill back well, milled to 1250, ran mill back and milled to 1265. Pulled mill and wash pipe had bailer parts and part of a 4-1/2" casing collar. We are out side of the 4-1/2" casing. Shut down.

08-01-95

Called the Kansas State Corporation Commission for plugging orders. Bruce Basye the State man from Hays on location 1:00 P.M. Rigged up L-K Wireline Inc. and perforated 3 hole at 945 and 180. Ran tubing to 1220 and spotted 50 sacks common cement, pulled tubing to 750, pumped 50sks 60/40 Poz with 150# Hulls, pulled tubing and pumped 100 sks. 60/40 pox 8% gel. down the casing, shut in pressure 300#, Finished 3:00 PM 08-01-95. Rigged down and moved to the Grtrell #-4

Thank you

*W. J. Luck*

W. J. Luck

RECEIVED  
STATE CORPORATION COMMISSION

AUG 1 1995

STATE CORPORATION COMMISSION  
WICHITA KANSAS