

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.
 Address: 250 N. Water, Suite 300
 Phone: (316) 267-3241 Operator License #: 30606
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 2/2/05 (Date)
 by: Rich Williams w/ KCC in Hays, KS (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 2904-10,2924-28,2942-48,2960-66 Depth to Top: _____ Bottom: _____ T.D. _____
 3045-47,3052-56,3062-66,3084-89 Depth to Top: _____ Bottom: _____ T.D. _____
 3141-47 Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-545-051-05621-00-00
 Lease Name: Hadley A
 Well Number: 1
 Spot Location (QQQQ): NE - SE - SE - KCC
330 990 Feet from North / South Section Line BEM
330 Feet from East / West Section Line 3-1-05
 Sec. 12 Twp. 11 S. R. 18 East West RBDMS
 County: Ellis
 Date Well Completed: 5/45
 Plugging Commenced: 2/2/05
 Plugging Completed: 2/2/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Conductor	Surface	91	15 1/2	91	0
	Surface	Surface	1087	10	1087	0
	Production	Surface	3328.5	7	3328.5	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run 2 7/8 tbg open-ended to 2114'. Allied mixed 290 sks 60/40 poz 10% gel. 300# hulls pumped dwn. tbg. cement circulated to pit. TOH with 2 7/8 tbg. Allied mixed 25 sks 60/40 poz 10% gel pump dwn. 10 3/4 to 500# pressured 15 3/8 to 500#. Allied mixed 130 sks 60/40 poz 10% gel 100# hulls pumped dwn. 7" to 500# shut in at 150#. Plugged witnessed by Rich Williams w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
 Address: 250 N. Water, Suite 300 ; Wichita, KS 67202
 Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.
 State of Kansas County, Sedgwick, ss.

RECEIVED
FEB 24 2005
KCC WICHITA

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



CRIBED and SWORN TO before me this 23rd day of February, 2005

Kristin Grady My Commission Expires: 2/06/08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Signature]

Federal Tax I.D.# [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: L

DATE <u>2-2-05</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START <u>12:15pm</u>	JOB FINISH <u>3:00pm</u>
LEASE <u>WAXEY</u>		WELL # <u>A-1</u>		LOCATION <u>HAYS N TO RIVER RD</u>		COUNTY <u>ELLIS</u>	STATE <u>Ks</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)		<u>3E 1/4 NW</u>					

CONTRACTOR MURFEN

TYPE OF JOB FTA

HOLE SIZE _____ T.D. _____

CASING SIZE 7" DEPTH _____

TUBING SIZE 2 1/2 DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT

AMOUNT ORDERED 360 @ 10% GEL

8 HULLS

USED 445

COMMON	<u>2107</u>	@	<u>8.30</u>	<u>2210.10</u>
POZMIX	<u>128</u>	@	<u>4.50</u>	<u>801.00</u>
GEL	<u>30</u>	@	<u>13.00</u>	<u>390.00</u>
CHLORIDE		@		
ASC		@		
HULLS	<u>8</u>	@	<u>20.00</u>	<u>160.00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>597</u>	@	<u>1.50</u>	<u>895.50</u>
MILEAGE	<u>.055/sk/mi</u>			<u>1477.80</u>
TOTAL				<u>5940.40</u>

EQUIPMENT

PUMP TRUCK CEMENTER MARK

345 HELPER STEVE

BULK TRUCK

222 DRIVER RUBIN

BULK TRUCK

378 DRIVER GARY

REMARKS:

290SK @ 2100' w/6 HULLS GEL CEMENT

PULL TUBING

25 SK @ 1034 PRES TO 500'

PRES 1538 TO 500'

130 SK DOWN 7" w/2 HULLS

MAX 500'

SHUT IN 150'

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 570.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 45 mi. @ 4.50 202.50

MANIFOLD _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 772.50

CHARGE TO: MURFEN

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

RECEIVED _____ @ _____

FEB 24 2005 _____ @ _____

KCC WICHITA _____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____